

TENDER FOR CONSTRUCTION OF DOUBLE-STOREY PRIMARY SCHOOL BLOCK

Tender No: EDU/2026/042 | Estimated Cost: Rs 1.85 Crore

1. SCOPE OF WORK

1.1 Construction of a double-storey (G+1) reinforced cement concrete framed school building with classrooms, staircase and toilets.

1.2 The building height shall be 2 storeys with 3.3 m floor-to-floor height.

2. CONCRETE WORK

2.1 All structural concrete shall be design-mix reinforced cement concrete of minimum characteristic compressive strength 25 MPa at 28 days.

2.2 Nominal maximum size of coarse aggregate shall be 20 mm, graded and free from dust and organic impurities.

3. CEMENT AND STEEL

3.1 Only Ordinary Portland Cement of 43 Grade shall be used for all RCC work.

3.2 Reinforcement shall be high strength deformed steel bars of grade Fe500, free from loose mill scale, rust and oil.

3.3 Minimum clear cover to reinforcement in columns and beams shall be 40 mm.

4. WATER SUPPLY AND SANITATION (Contd.)

4.1 Internal water supply shall use galvanized iron pipes with a minimum overhead storage capacity of 5000 litres for the toilet block.

4.2 Sanitary fixtures shall be vitreous china, minimum 2 sets per toilet unit.

5. ELECTRICAL WORK

5.1 Internal electrical wiring shall be concealed copper conductor wiring with PVC conduits, with miniature circuit breakers for each classroom circuit.

5.2 Earthing shall be provided with copper earth electrodes and the earth resistance shall not exceed 5 ohm at the time of testing and commissioning.

6. TESTING AND COMMISSIONING

6.1 Concrete cubes shall be tested at 7 days and 28 days for every 20 cubic metres of concrete poured at site.

6.2 The contractor shall submit test certificates for cement, steel and electrical safety before handing over the building.